

# Invitation of Quotation for

Work regarding installation of tiles in a room at  
RT ward, 1st floor Oncology building, AIIMS  
Jodhpur

Inquiry No.	AIIMS Jodh./Engg./Q.N./2024-25/01
Inquiry Issue Date	06-06-2024
Last Date of Submission	13-06-2024 at 03:00 PM



**All India Institute of Medical Sciences, Jodhpur**  
Basni Phase - II, Jodhpur – 342005, Rajasthan  
Telefax: 0291- 2012978 [www.aiimsjodhpur.edu.in](http://www.aiimsjodhpur.edu.in)

---



**ALL INDIA INSTITUTE OF MEDICAL SCIENCES, JODHPUR**  
**अखिल भारतीय आयुर्विज्ञान संस्थान, जोधपुर**

Quo. No. AIIMS Jodh./Engg./Q.N./2024-25/01

Dated: 06-06-2024

**QUOTATION NOTICE**

Sealed Quotations are invited from the vendor/supplier/contractor/agency by the undersigned on behalf of the Executive Director, AIIMS Jodhpur for "**Invitation of Quotation for Work regarding installation of tiles in a room at RT ward, 1st floor Oncology building, AIIMS Jodhpur.**" Description of *items* and bill of quantities is given overleaf. The last date for submission of quotations is 06-06-2024 up to 3:00 P.M.

**General Terms and Conditions:**

1. The quotations received after **13-06-2024** and unsealed shall not be entertained under any circumstances whatsoever. In case of postal delay, this Institute will not be responsible. The offer Submitted Fax/Email shall not be considered and no correspondence will be entertained in this matter.
2. Quotations must be in the enclosed prescribed Performa on the letterhead of the firm duly signed by the Proprietor/Partner/Director or their Authorized Representative, in case of signing of quotation by the authorized representative letter of authorization must be attached with the quotation. Quotation must be dropped in "Quotation Box" located in Administration Block of AIIMS, Jodhpur.
3. Rates must be quoted in "Indian Rupees" and as per the format, specified taxes extra if any must be written separately.
4. Rates must be quoted FOR basis (including Freight charges, Insurance, installation etc.)
5. No overwriting or cutting is permitted in the rate. If found, the quotation shall be summarily rejected.
6. The rates quoted must be valid for 90 days minimum from the date of opening of the quotation.
7. Becoming L-1 will not be the criteria for awarding of work unless the rates are reasonable & justified and the same will be decided on composite basis.
8. RTGS/NEFT details need to be furnished by the supplier with the quotation on the letterhead of supplier/firm/agency.
9. The firm/agency may satisfy the following conditions and attach self-attested copy of the same with the quotation:
  - The firm shall have valid GSTIN and IT PAN.
10. Quotations qualified by such vague and indefinite expressions such as "subject to prior confirmation", "subject to immediate acceptance" etc. will be treated as vague offers and rejected accordingly. Any conditional quotation shall be rejected summarily.
11. The quotation will not be considered in case of incomplete information.
12. The time allowed for carrying out the above work is **30 days** from date of issue of work order.
13. If the supplier/vendor/contractor fails to carrying out the above work on or before the stipulated date, then a penalty at the rate of 0.5 % per week of the total order value shall be levied subject to maximum of 10% of the total order value.
14. Payment Terms: Payment will be only after satisfactory completion of work and after inspection by the AIIMS Jodhpur.
15. Disputes: In the event of any dispute or disagreement arising between the contractors and any other department of AIIMS Jodhpur with regards to the interpretation of "Terms & Conditions" of this inquiry, the same shall be referred to the Director, AIIMS Jodhpur whose decision will be final and binding upon the contractor.
16. AIIMS, Jodhpur reserves the right to increase or decrease quantity and /or amount of work. Decision of Quantity of work in the AIIMS, Jodhpur will be final in this regard.
17. AIIMS, Jodhpur reserves the right to reject any quotation or part or the whole of inviting quotation process without assigning any reason. Decision of the AIIMS, Jodhpur will be final in this regard.

**Special Terms & Conditions:**

1. Bidder must quote rate in Price Bid Form provided in **Annexure-A** on the letterhead of the firm.

2. It is responsibility of the contractor to Supply, Installation, Testing and Commissioning (SITC) of Air Conditioners at required location, complete with transportation, labour including connection, gas charging, testing, earthing etc. as required and nothing shall be paid extra in this account.
3. The contractor shall be fully responsible for the safety of all labour/employees employed on the work.
4. The contractor shall have to arrange all type of tools and special T&P etc. at his own cost as required to carry out work for which nothing extra shall be paid to the contractor by the department.
5. There shall be no liability on the AIIMS Jodhpur to pay any compensations arising out of any labour dispute or accident etc. at site.
6. Workers engaged by the contractor for execution of work shall be liability of the contractor.
7. Any damage done by the contractor or his workmen to any existing work during the course of execution of the work shall be made good by him at his own cost.
8. Contractor shall clear the site thoroughly of all rubbish etc. left out of his materials immediately on completion of the work and properly clean the site around the building to the satisfaction of the Engg. -in- charge. Otherwise the site will be cleared by the department at his risk & cost to remove and clean the site.

**(Executive Engineer, Civil)**

---

**[On the letterhead of firm]**  
**ANNEXURE "A"**  
**Price Bid Form**

**To,**  
**Executive Engineer (Civil),**  
**AIIMS, Jodhpur.**

Dear Sir,

- I/We

Submitted

the quotation for **Quotation No. AIIMS Jodh./Engg./Q.N./ 2024-25/01, Dated: 06-06-2024** at AIIMS Jodhpur".

- I/We thoroughly examined, understood and accepted terms & conditions given in the enquiry document, failing which my quotation will be rejected out rightly.
- I/We hereby offer to supply at the following rates.

S.No	Description of work	Unit	Total Qty	Rate	Amount
	<b>Civil Works:</b>				
1	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix)	Cum	5.68		
2	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved.	Cum	5.68		
3.	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:3:6 (1 Cement : 3 coarse sand (zone-III) : 6 graded stone aggregate 20 mm nominal size derived from natural Sources.)	Cum	5.68		
4.	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	Sqm	45.30		
5	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the	Sqm	56.80		

	manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joints with white cement and matching pigments etc., complete. Size of Tile 800x800 mm				
6	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joints with white cement and matching pigments etc., complete. Size of Tile 600x600 mm	Sqm	48.72		
7	Deduct for not using 20 mm thick cement mortar 1:4 (1 cement : 4 coarse sand) bedding in laying of floor tiles and jointing with grey cement slurry @ 3.3 kg/ sqm.	Sqm	-61.32		
8	Fixing glazed/ Ceramic/ Vitrified floor tiles with cement based high polymer modified quick-set tile adhesive (Water based) conforming to IS: 15477, in average 3mm thickness.	Sqm	63.42		
9	Distempering with 1st quality acrylic distemper, having VOC (Volatile Organic Compound ) content less than 50 grams/ litre, of approved brand and manufacture, including applying additional coats wherever required, to achieve even shade and colour. Old work (One or more coat)	Sqm	102.1		
10	Distempering with 1st quality acrylic distemper, having VOC (Volatile Organic Compound ) content less than 50 grams/ litre, of approved brand and manufacture, including applying additional coats wherever required, to achieve even shade and colour. Old work (One or more coat)	Sqm	102.1		

**Total Amount inclusive of GST (in figure).....**

**Total Amount inclusive of GST (in words).....**

.....

**L-1 will be decided on composite basis. Becoming L1 will not be the criteria for awarding of work unless the rate are reasonable & justified.**

Date \_\_\_\_\_

Place \_\_\_\_\_

Signature of Authorised Person: \_\_\_\_\_

Name of the Firm/Agency: \_\_\_\_\_

\_\_\_\_\_  
Phone No: \_\_\_\_\_

Firm's GSTIN: \_\_\_\_\_

Firm's PAN No: \_\_\_\_\_

Bank Account No: \_\_\_\_\_

Bank Name: \_\_\_\_\_

Branch: \_\_\_\_\_ IFSC Code \_\_\_\_\_

---